



PANEL HOLD DOWN OPTION:  
 CONCRETE EMBEDDED  
 SIMPSON PAHD/HPAHA  
 HOLDDOWN STRAPS. ATTACH  
 TOP 2 HOLES WITH #6  
 SCREWS, ALL ELSE MAY USE  
 16d WHERE SOLID LUMBER  
 BACKING IS AVAILABLE,  
 FILL ALL HOLES

ANCHOR BOLT AS  
 REQUIRED PER  
 ENGINEER

CONCRETE STEM WALL  
 PER ENGINEER. 8" WIDE  
 MIN. AND 18" MIN. BELOW  
 GRADE

8"X16" MIN. CONCRETE  
 FOOTING W/ 2 CONT.  
 REBAR PER ENGINEER

1" DIA. WIRING  
 CHASE

SIPS WALL

2x PRESSURE  
 TREATED SILL PLATE

4" CONCRETE SLAB OVER  
 COMPACTED  
 AGGRAGATE/SAND  
 AS REQ'D PER ENGINEER

2x 8d NAILED/STAPLED  
 @ 6" O.C. BOTH SIDES  
 IN EACH ROUTED  
 PANEL END

**1** FOUNDATION DETAIL  
 D36 1" = 1'-0"

**Greenix<sup>®</sup> Panels**  
**Greener. Cleaner. Safer. Stronger**

SIP SUPPLY, LLC  
 P. O. Box 671032  
 MARIETTA, GA 30066  
 1-770.776.6198  
<http://SIPsupply.com>

This document is an instrument of service, and as such, remains the property of SIP Supply, LLC. Permission for use can be extended only by written agreement with SIP Supply, LLC. COPYRIGHT 2003